BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P, Bangalore

Tender Notification No, RRND/EE/Tend/01/2014-15,date: 04.06.2014

E-procurement No: BBMP/2013-14/OW/WORK_INDENT10733/CALL-4

SCHEDULE-B

Name of Work : Providing RCC Drain and Improvements to Foot path at 1st A" cross Sharadambhanagara in ward No.16

Sl.NO	Qty	Description of Work	Unit	Tender Rate	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	335.28	Earth work execavation for foundation of buildings, water supply, sanitary Lines and electrical conduits either in pits or in trenches 1.5m and above in width , in hard soil not exceeeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the execavated soil clear from edges of execavation with lead upto 50 m. after breaking of clods copmlete as per specifications	cum	239	Rupees Two Hundred Thirty Nine Only
2	435.86	Lead for earthwork and disposal of debris shall be payable at carriage rates by mechanical means including loading and unloading for earthwork (upto 3.5 kms) complete with all lead & lift & as the direction of the Engineer in-charge	cum	81	Rupees Eighty One Only
3	43.56	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180kgs, with 40mm and down size graded granite metal, coarse aggregates @ 0.85 cum & fine aggregates @ 0.57cum machine mixed, concrete laied in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all meterials, labour, HOM of machinery, curing complete as per specifications	sqm	4504	Rupees Four Thousand Five Hundred And four Only
4	633.6	Providing and removing centering, shuttering, strutting, propping etc, and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all meterials, labour complete as per specification	cum	285	Rupees Two Hundred and Eighty Five Only

Scanned by CamScanner